

# FDOT SR 688 FROM LAKE SIMENOLE BYPASS CANAL TO EAST OF WILD ACRES ROAD



## CLIENT

Conalvias USA LLC  
9225 Ulmerton Road, Suite R  
Largo, FL 33771  
Rick Sheppard

## ENGINEER

King Engineering  
4921 Memorial Highway  
Suite 300  
Tampa, FL 33634  
Tel. (407) 896-8608

## PROJECT START/COMPLETION

2015-2016

## INITIAL / FINAL COST

\$846,886.00 / \$846,886.00

## KEY STAFF

Javier Garzon

## Project Description

The project consisted of the widening of SR 866 (Ulmerton Road) at the bypass channel from Lake Seminole and Wilde Acres Road. We worked as a subcontractor to Conalvias USA for the sanitary sewer installation. Our project consisted of the installation of 4,274 LF of 8" to 12" DIP gravity sewer ranging from 6-feet deep to 18-feet deep, 15 sanitary sewer manholes and 10 cleanouts. Approximately 1,661 LF was installed at a depth of 14' to 18' Feet Deep. Our cost included the installation only. Materials were purchased by the Prime Contractor.



# RPU

GENERAL & ENGINEERING  
CONTRACTORS