


ORANGE COUNTY RIO PINAR LAKES FORCE MAIN IMPROVEMENTS – DISTRICT 3 IFB NO. Y19-762-TA



CLIENT

Orange County
9150 Curry Ford Road
Orlando, FL 32825
James Montalvo
Tel. (407) 254-9900

ENGINEER

BFA Environmental Consultants
1230 E. Hillcrest Street, Suite 100
Orlando, FL 32803
Tel. (407) 896-8608

PROJECT START/COMPLETION

October 2019 – June 2020

INITIAL / FINAL COST


\$1,069,462.73 / \$1,036,085.04

KEY STAFF

Javier Garzon, Principal-In-Charge
Raidel Perez, Superintendent
Alphonso Brown, MOT
Fred Ward, Safety Manager

Project Description

Project consisted of approximately 4,200 LF of 12-inch wastewater force main in the Rio Pinar Lakes neighborhood. The Scope of work included the following: approximately 4,200 linear feet of 12-inch diameter PVC force main via open cut; approximately 130 linear feet of 24-inch steel casing pipe with 12-inch PVC force main by a jack and bore approximately 20-feet deep; installed two (2) temporary 24-inch line stops with 16-inch bypass outlets on the existing ductile iron potable water main to facilitate completion of the proposed force main bore and jack on Curry Ford Road including bypass piping and replacement of the existing 24-inch water main; Perform connections to existing force main systems; removed approximately 2,300 LF of existing 6-inch PVC force main; hardscape restoration; roadway restoration; and swale reconstruction.



RPU

GENERAL & ENGINEERING
CONTRACTORS